**Errata**

# NFPA 13

## Standard for the Installation of Sprinkler Systems

**2007 Edition**

**Reference: Various**
**Errata No.: 13-07-1**

The Automatic Sprinkler Systems committee notes the following errors to the first printing of the 2007 edition of NFPA 13, *Automatic Sprinkler Systems.*

*1. Revise Fire Department Connection reference in Index (p. 369) as follows:*

a) Delete 8.17.5.2 and replace with 8.17.2

b) Change the definition reference from 3.12.4 to 3.8.1.4

2. *Figures A.9.3.5(a) and A.9.3.5(b) bottom section as follows:*

Sprinkler System Load Calculation [$\underline{F_{pw}}$ =____$W_p$ (default 0.5)]

Change existing $F_p$ = _____$W_p$ to $\underline{F_{pw}}$ =_____$W_p$

Change existing $F_p \times 1.15$ to $\underline{W_p} \times 1.15$

*3. Figure A.9.3.5(b):*

Change page number 2 of 2 to 1 of 1

*4. Paragraph 10.1.1 change "and" to "or".*

*5. Revise A.12.1.3.4 by adding a vertical line and in the 3rd paragraph 2nd line reference to K-5.6 should be K-11.2 per ROP 13-506.*

*6. Revise Table 15.4.1 by*

*(a) On page 135, extending the line in the first two columns between the maximum Storage Height of 40 ft and 20 ft.*

*(b) On page 136, in the second column delete the words "Cartoned unexpanded plastic" and the line directly below.*

*7. Revise 16.2.5.1.2(7) and 17.2.5.1.2(7) as follows:*

(7) The aisle widths shall be at least 7 ft <u>7 ½ ft</u> (2.3 m).

*8. Table 16.3.2.1(a) ands (b): Revise Note as follows:*

Copyright National Fire Protection Association
Provided by IHS under license with NFPA
No reproduction or networking permitted without license from IHS
Not for Resale

*High temperature rated sprinklers shall be used. Dry system water delivery shall be determined in accordance with ~~7.2.3.4~~ 7.2.3.6 or 7.2.3.7 with a ~~minimum~~ maximum time of water delivery of 30 seconds with four sprinklers initially open.

*9. Figure 17.1.2.1 – Add vertical rule to the figure notes.*

*10. Table 18.4(d) – Correct note references in Table 18.4(d). In seventh column, change the title to read* "Number of Sprinklers". *In rows 1 through 8 of that column change the note reference to read* "(See Note 2)". *In row 9 of that column change the note reference to read* "(See Note 3 and 4)".

*11. Revise last column of Table 19.1.2.2 by changing* "See Note 3" *to* "See Note 2".

*12. Paragraph 21.7.2.3.4 Change (100cm) to (10cm)*

*13. Annex C – C.9 change (4.65km$^2$) to (4,645 m$^2$) and (9.29 km$^2$) to (9.290 m$^2$)*

*14. Delete reference to Compact Shelves in the Index (p. 366).*

**Issue Date: August 13, 2007**

Copyright © 2007 All Rights Reserved
NATIONAL FIRE PROTECTION ASSOCIATION

--`,,```,,,,````-`-`,,`,,`,`,,`---

Copyright National Fire Protection Association
Provided by IHS under license with NFPA
No reproduction or networking permitted without license from IHS
Not for Resale