Tentative Interim Amendment

NFPA 409

Standard on Aircraft Hangars

2004 Edition

Reference: 7.5.8 & A.7.5.8
TIA 04-1 (NFPA 409)
(SC 05-4-37/Log No. 810)

Pursuant to Section 5 of the NFPA Regulations Governing Committee Projects, the National Fire Protection Association has issued the following Tentative Interim Amendment to NFPA 409, *Standard on Aircraft Hangars*, 2004 edition. The TIA was processed by the Airport Facilities Committee, and was issued by the Standards Council on April 14, 2005, with an effective date of May 4, 2005.

A Tentative Interim Amendment is tentative because it has not been processed through the entire standards-making procedures. It is interim because it is effective only between editions of the standard. A TIA automatically becomes a proposal of the proponent for the next edition of the standard; as such, it then is subject to all of the procedures of the standards-making process

1. Replace the existing text in 7.5.8 with the following:

7.5.8 The low-level foam system shall be designed to achieve distribution of foam over the entire aircraft storage and service area. The design objective shall be to achieve coverage of the entire aircraft storage and servicing area to within 1.5 m (5 ft) of the perimeter walls and doors within 3 minutes of system actuation.

2. Delete the annex material A.7.5.8

Copyright © 2005 All Rights Reserved
NATIONAL FIRE PROTECTION ASSOCIATION

Copyright National Fire Protection Association
Provided by IHS under license with NFPA
No reproduction or networking permitted without license from IHS
Not for Resale